



सत्यवती महाविद्यालय
Satyawati College
(दिल्ली विश्वविद्यालय)
(University of Delhi)



अशोक विहार, फेज - III, दिल्ली - 110052 | Ashok Vihar, Phase - III, Delhi - 110052

Website : www.satyawati.du.ac.in | E-mail : principal@satyawati.du.ac.in | Phone : 011 - 27133520 / +91 9310363484

NAAC ACCREDITED 'A+' GRADE

SC/Admim/50/2026

Date - 16/04/2026



Notice for Inviting Spot Quotations

Percentage rate spot quotations are here by invited from contractors enlisted with CPWD, MES, Railways and working contractors of University of Delhi for the work of "Wall tile fixing in Auditorium at Satyawati College, University of Delhi" so as to reach the college office by 1.00 p.m. on 20.04.2026.

Financial Bid/Estimate is attached as Annexure-A

Conditions:

1. The work is to be carried out as per CPWD specifications.
2. The time allowed completing the work 5 days.
3. No water charges to be deducted from the bill
4. The rates quoted should be inclusive of all taxes and duties & should be written both in words and figure.
5. The contractor should see the site before quoting the rate.
6. Undersigned reserves the right to reject any or all the quotation without assigned any reason thereof.


Principal


I/we _____ hereby agree to execute the @ _____ % above/ below at par the estimate cost (Annexure-A).

Signature of the Contractor

Name _____

Address _____

Contact No. _____

Annexure-A

S.No.	Description of items	Qty.	Unit	Rate	Amount
1	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete	35	sqm	1268	44380
2	Disposal of moorum/building rubbish/ melba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead up to 10 km for all lifts, complete as per directions of Engineer-in-charge.	3	cum	494.1	1482.3
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	35	sqm	25.15	880.25
4	Hacking of wall including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	35	sqm	73.4	2569.0
TOTAL AMOUNT					49311.55